



YOGI VEMANA UNIVERSITY

Vemanapuram, Kadapa – 516 005 (A.P., INDIA)

No. YVU/ED/KDP/PE/JTO / Admin. Building / Shifting of R.O. Plant/Web
Quotation/2025-26, Dt.08.01.2026.

To,

The Eligible Contractors.

Sub: Yogi Vemana University, Kadapa- Engineering Department - "Providing Brick Masonry Wall for Creation of Food Serving Counter at New Canteen Building in Yogi Vemana University, Kadapa"- Call for Quotations- Request - Reg.

-o0o-

Sealed quotations are invited from eligible and experienced Civil / Plumbing Contractors for execution of the work "Shifting and Re-installation of Existing R.O. Water Plant from 21st Century Gurukulam Buildings to New Administrative Building, Yogi Vemana University, Kadapa, including brick masonry, plastering, flooring, painting, grills and other miscellaneous works as directed by the Engineer-in-Charge.:

Sl.No	Description of Item	QTY	Unit	Amount
1.	Dismantling, clearing away and carefully stacking useful materials for re-use and disposal of unserviceable materials with 100m lead us directed by Executive Engineer duly taking actual premeasurements before dismantling including all labour charges.	1.26	Cum	
2	Masonry work in CM(1:6) prop (Cement : Sand) in superstructure with fly ash cement / lime solid blocks of size 290mm x 22.5mm x 140mm from approved source having minimum crushing strength of 50 Kg/Sqm. including cost and conveyance of all materials like cement, sand, fly ash cement / lime solid blocks, water etc., to site, labour charges, the mixing cement mortar, scaffolding charges, constructing masonry, lift charges, curing, etc., complete for finished item of work. (APSS No. 501 & 504)	1.08	cum	
3	Plastering 12mm thick single coat in CM(1:5) using screened sand including cost and conveyance of all materials like cement, sand, water etc., to site and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, curing as directed by Engineer-in-charge etc., and complete for finished item of work	11.53	Sqm	
4	Plastering 20mm thick single coat in CM(1:5) using screened sand including cost and conveyance of all materials like cement, sand, water etc., to site and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, curing as directed by Engineer-in-charge etc., and overheads & contractors profit complete for finished item of work for basement (SS 901, 903 & 904)	24.21	Sqm	
5	Plain Cement concrete Grade M20 - Nominal Mix using 20mm metal hand mixing from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc., to site including all charges laying concrete in foundations and under flooring bed, ramming in 15 cm layers finishing top surface to line and level etc., complete for finished item of work.	0.26	Cum	
6	Labour Charges for removing and refixing with complete servicing of the MS windows/Grills including cost and conveyance of all materials to site, incidental, operational and all labour charges etc., complete for finished item of work in all floors.	14.67	Sqm	
7	Painting two coats with synthetic enamel paint Gr-I having VOC (Volatile Organic Compound) content less than 50 grams/litre in old iron work including cost and conveyance of all materials to site, incidental, operational and all labour charges and overheads & contractors profit etc., complete for finished item of work in all floors. (SS No. 1201, 1212, 1207)	14.67	Sqm	

(P.T.O)



Sl.No	Description of Item	QTY	Unit	Amount
8	Supply & application of one coat of acrylic emulsion paint having VOC (Volatile Organic Compound) content less than 50 grams/litre for internal walls including cost and conveyance of all materials to site, incidental, operational and all labour charges etc., complete for finished item of work in all floors. At Administrative Building (R.O Plant)	49.06	Sqm	
9	Supply & application of two coats of acrylic emulsion paint having VOC (Volatile Organic Compound) content less than 50 grams/litre for internal walls including cost and conveyance of all materials to site, incidental, operational and all labour charges etc., complete for finished item of work in all floors. At Administrative Building (R.O Plant)	8.90	Sqm	
10	Supply and fixing of MS-Powder Coated Aldrop (IS:2681) 300 mm long including cost and conveyance of all materials to site incidental, operational and all labour charges, complete for finished item of work in all floors. At Administrative Building (R.O Plant)- grill	1.00	No.	
11	Supply of Tractor including cost and conveyance of all materials incidental, operational and all labour charges, complete for finished item of work. At Administrative Building shifting cement debris	2.00	Hrs	
	Total			

Terms and Conditions:

1. Eligibility:

The contractors registered with Government Departments/ Public Sector Undertakings are eligible to participate.

2. Quotation Basis:

Rates shall be quoted on a lump-sum basis for the work component only, inclusive of all materials, labour, transport, tools & plants, and all incidental charges but exclusive of GST, NAC @ 0.1% and Seigniorage Charges, as these statutory charges will be paid on actuals by the University as per prevailing Government norms.

3. Work Completion:

The work shall be completed within 7 days from the date of issue of the work order.

4. Payment:

Payment will be made after satisfactory completion and certification by the Engineering Department, Yogi Vemana University, Kadapa.

5. Submission of Quotations:

Sealed quotations, superscribed as "Quotation for Shifting and Re-installation of R.O. Water Plant - YVU, Kadapa" should reach the office of the Registrar, Yogi Vemana University, Kadapa on or before 20.01.2026 at 3:00 P.M.

6. Right of Rejection:

The University reserves the right to reject any or all quotations without assigning any reason.


 I/c REGISTRAR
 REGISTRAR
 YOGI VEMANA UNIVERSITY
 KADAPA-516005.

Copy to the Director, IT & Networking Cell, YVU, Kadapa with a request to place the call letter in the University Web site.

Copy to Notice Board.

Copy to file.