



YOGI VEMANA UNIVERSITY

Vemanapuram, Kadapa – 516 005 (A.P., INDIA)

No. YVU/ED/KDP/PE/JTO/ New Admin. Building / Miss. Civil Works / Web Quotation/
2026-27, Dt. 17.04.2026.

To,

All Reputed Firms / Contractors.

Sub: Yogi Vemana University, Kadapa- Engineering Department – Providing brick masonry and miscellaneous works for lift portion at New Administrative Building, Yogi Vemana University, Kadapa– Calling for Quotations – Reg.

--o0o--

Sealed quotations are hereby invited from reputed, experienced civil contractors / agencies for the work of “Providing brick masonry and miscellaneous works for lift portion at New Administrative Building, Yogi Vemana University, Kadapa.”

Details of Requirement:

S.No.	Description of Item	Qty	Rate	Amount
1	Reinforced Masonry for partition walls (100 mm thick) in CM (1:4) prop. (Cement : Sand) using fly ash cement / lime solid blocks of size 290mm x 100mm x 140mm having minimum compressive strength of 50 Kg/Sq.cm and placing 2 Nos. of 6mm M.S plain rods in every third layer with free ends of the reinforcement pegged into mortar joints of main brick walls where applicable including cost and conveyance of all materials like cement, steel, sand, fly ash cement / lime solid blocks, water etc., to site, all operational, incidental charges such as labour charges for mixing cement mortar, scaffolding charges, constructing masonry, lift charges, curing, etc., but excluding cost of steel and its fabrication charges complete for finished item of work. (APSS No. of 509)			
a	Ground Floor	11.15 /	Sqm	
b	First Floor	3.50 /	Sqm	
c	Second Floor	2.00 /	Sqm	
2	Masonry work in CM(1:6) prop (Cement : Sand) in superstructure with fly ash cement / lime solid blocks of size 290mm x 225mm x 140mm from approved source having minimum crushing strength of 50 Kg/Sqcm. including cost and conveyance of all materials like cement, sand, fly ash cement / lime solid blocks, water etc., to site, labour charges, like mixing cement mortar, scaffolding charges, constructing masonry, lift charges, curing, overheads and contractor profit etc., complete for finished item of work. (APSS No. 501 & 504). – Second Floor	0.10 /	Cum	
3	Plastering 12mm thick single coat in CM(1:5) using screened sand including cost and conveyance of all materials like cement, sand, water etc., to site and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, curing as directed by Engineer-in-charge etc., complete for finished item of work (SS 901,903 & 904)	15.50	Sqm	
a	Ground Floor	15.50 /	Sqm	
b	First Floor	6.00 /	Sqm	
c	Second Floor	6.60 /	Sqm	
4	Plastering 20mm thick single coat in CM(1:5) using screened sand including cost and conveyance of all materials like cement, sand, water etc., to site and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, curing as directed by Engineer-in-charge etc., and overheads & contractors profit complete for finished item of work for basement. (SS 901,903 & 904)	110.00	Sqm	



S.No.	Description of Item	Qty	Rate	Amount
5	Supply & application of one coat of acrylic emulsion paint having VOC (Volatile Organic Compound) content less than 50 grams/litre as approved by Engineer-In-Charge, to give an even shade after thoroughly brushing the old surface to remove all dirt and remains of loose powdered materials, for internal walls including cost and conveyance of all materials to site, sales & other taxes, incidental, operational and all labour charges etc., and complete for finished item of work in all floors.	350.00	Sqm	
	Total Amount			
	CGST @ 9%			
	SGST @ 9%			
	Grand Total			

Terms and Conditions:

1. The bidder shall have relevant experience in civil maintenance and repair works.
2. The quoted rates shall be inclusive of all materials, labour, transportation, taxes, and incidental charges.
3. The work shall be executed as per standard specifications and instructions of the Engineering Department.
4. The work shall be completed within the stipulated time after issue of work order.
5. Payment will be made only after satisfactory completion and certification by the Engineering Department.
6. The contractor shall ensure quality workmanship and proper finishing.
7. Any additional works shall be carried out only with prior approval.
8. The University reserves the right to accept or reject any or all quotations without assigning any reason.

Note: "The sealed quotations, superscribed as 'Quotation for Miss. Civil Works at New Admin. Building – YVU, Kadapa– YVU, Kadapa', shall be sent by post or courier and delivered to the Office of the Registrar, Yogi Vemana University, Kadapa, on or before 25.04.2026 during office hours."

I/c REGISTRAR

REGISTRAR
YOGI VEMANA UNIVERSITY
KADAPA-516005.

Copy to the Director, IT & Networking Cell, YVU, Kadapa with a request to place the call letter in the University Web site.
Copy to Notice Board.
Copy to file.