



YOGI VEMANA UNIVERSITY

Vemanapuram, Kadapa – 516 005 (A.P., INDIA)

No. YVU/ED/KDP/PE/JTO/ Sir. C.V. Raman Science Block/Certain Repair Works/Room Nos. to 121, 208,223,224, 234, 235& 236/ Web Quotation/ 2026-27,Dt.15.04.2026.

To,

All Reputed Firms / Contractors.

Sub: Yogi Vemana University, Kadapa- Engineering Department – Providing miscellaneous civil repairs and maintenance works in Geology, Microbiology, Materials Science & Nanotechnology, and Botany Departments located in Sir C.V. Raman Science Block, Yogi Vemana University, Kadapa– Calling for Quotations – Reg.

--o0o--

Sealed quotations are hereby invited from reputed, experienced civil contractors / agencies for the work of “Providing miscellaneous civil repairs and maintenance works in Geology, Microbiology, Materials Science & Nanotechnology, and Botany Departments located in Sir C.V. Raman Science Block, Yogi Vemana University, Kadapa.”

Details of Requirement:

S.No.	Description of Item	Qty	Rate	Amount
1	Reinforced Masonry for partition walls (100 mm thick) in CM (1:4) prop. (Cement : Sand) using fly ash cement / lime solid blocks of size 290mm x 100mm x 140mm having minimum compressive strength of 50 Kg/Sq.cm and placing 2 Nos. of 6mm M.S plain rods in every third layer with free ends of the reinforcement pegged into mortar joints of main brick walls where applicable including cost and conveyance of all materials like cement, steel, sand, fly ash cement / lime solid blocks, water etc., to site, all operational, incidental charges such as labour charges for mixing cement mortar, scaffolding charges, constructing masonry, lift charges, curing, etc., but excluding cost of steel and its fabrication charges complete for finished item of work. (APSS No. of 509)			
a	Ground Floor	2.90 Sqm		
b	First Floor	34.50 Sqm		
c	Second Floor	1.40 Sqm		
2	Plastering 12mm thick single coat in CM(1:5) using screened sand including cost and conveyance of all materials like cement, sand, water etc., to site and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, curing as directed by Engineer-in-charge etc., complete for finished item of work (SS 901,903 & 904)			
a	Ground Floor	2.90 Sqm		
b	First Floor	34.15 Sqm		
c	Second Floor	8.70 Sqm		
3	Supply & application of one coat water based cement primer of interior grade I and two coats of acrylic emulsion paint having VOC (Volatile Organic Compound) content less than 50 grams/litre for internal walls including cost and conveyance of all materials to site, incidental, operational and all labour charges etc., complete for finished item of work in all floors.	41.85 Sqm		



S.No.	Description of Item	Qty	Rate	Amount
4	Flooring with non-skid red or white full body Ceramic floor tiles of size 450 mm x 450 mm and thickness between 7-8 mm 1st quality conforming to IS:13711, IS:13712, IS:13630 (Parts 1 to 15) of any colour and finish in all shades and designs as approved by Engineer-in-charge, set over base coat of cement mortar (1:8), 12mm thick using screened sand over CC bed already laid or RCC roof slab, including neat cement slurry of honey like consistency spread @ 3.3 Kgs per sqm & jointed neatly with white cement paste to full depth mixed with pigment of matching shade, including cost of all materials like cement, screened sand, water and tiles etc., complete for finished item of work. (APSS No.701 & 707)	4.70 Sqm		
5	Supply of fresh air exhaust fan of light duty 250V A.C.50Hz. 225 mm (9") Metallic blades, wire mesh, etc., complete.	1.0 No.		
6	Labour charges for fixing of Exhaust fan in wall with necessary connections and masonry work of making hole, finishing etc., complete.	1.0 No.		
	Total Amount			
	CGST @ 9%			
	SGST @ 9%			
	Grand Total			

Terms and Conditions:

1. The bidder shall have relevant experience in civil maintenance and repair works.
2. The quoted rates shall be inclusive of all materials, labour, transportation, taxes, and incidental charges.
3. The work shall be executed as per standard specifications and instructions of the Engineering Department.
4. The work shall be completed within the stipulated time after issue of work order.
5. Payment will be made only after satisfactory completion and certification by the Engineering Department.
6. The contractor shall ensure quality workmanship and proper finishing.
7. Any additional works shall be carried out only with prior approval.
8. The University reserves the right to accept or reject any or all quotations without assigning any reason.

Note: "The sealed quotations, superscribed as 'Quotation for Civil Repair Works at Sir C.V. Raman Science Block - YVU, Kadapa- YVU, Kadapa', shall be sent by post or courier and delivered to the Office of the Registrar, Yogi Vemana University, Kadapa, on or before 23.04.2026 during office hours."



I/c REGISTRAR

Copy to the Director, IT & Networking Cell, YVU, Kadapa with a request to place the call letter in the University Web site.

Copy to Notice Board.

Copy to file.

REGISTRAR
YOGI VEMANA UNIVERSITY
KADAPA-516005.