



YOGI VEMANA UNIVERSITY

Vemanapuram, Kadapa – 516 005 (A.P., INDIA)

No. YVU/ED/KDP/PE/JTO/ New Admin., Building/1.5 Ton A.C. & Cuboid Ceiling Fan/
Web Quotation/ 2026-27, Dt.15.04.2026.

To,

All Reputed Authorized Dealers / Suppliers / Agencies.

Sub: Yogi Vemana University, Kadapa- Engineering Department – Electrical Section –
Providing New 1.5 Ton Air Conditioner and Cuboid Ceiling Fan in the Guest Room and Senate
Hall at New Administrative Building, Yogi Vemana University, Kadapa – Calling for Quotations
– Reg.

--o0o--

Sealed quotations are hereby invited from reputed, experienced and authorized dealers / suppliers /
electrical contractors for the work of “Providing New 1.5 Ton Air Conditioner and Cuboid Ceiling Fan in the
Guest Room and Senate Hall at New Administrative Building, Yogi Vemana University, Kadapa”.

Details of Requirement:

S.No.	Description of Item	Qty	Rate	Amount
1	Supply and Transportation of 1.5 Ton Split type Air-Conditioner, fitted with Hermetically sealed compressor, Operating on refrigerant R-22 / Non - CFC High wall mounting confirming to IS: 1391, suitable for operation on 230V, 50 Hz., Single phase, A.C Supply capable of performing Cooling, Dehumidifying, Air Circulating, Filtering with cooling and condensing units, with 5 Mtr of required size of copper piping duly insulated and 3 core copper flexible chord of required length etc., complete. Makes: Blue Star / Daikin / Hitachi / Voltas / Carrier / LG / Lloyd (prevailing models in the market)	01 No.		
2	Supply and erecting fully automatic line voltage stabilizer for operation on input voltage 200 to 250V. rated for 5 KVA maximum load and time delay model with Volt meter, selector switch, 6A / 16A flush type, 5 pin socket for out put and with 3 core flexible chord and 3 pin 6/16A plug top suitable for refrigerator for continuous operation including cost and conveyance of all materials and all labour charges etc., complete. Makes: V-Guard / Real Guard / Uni Stab / ITL.	01 No.		
3	Supply, Fabrication of 1set MS bracket suitable for fixing outdoor unit of split AC unit.	01 No.		
4	Supply, Transportation & Fixing of Cuboid Ceiling Fan 2x2	03 Nos.		
5	Wiring with 2 runs of 14/0.3mm (1.0 Sq.mm) Fire Retardant (FR) P.V.C. insulated flexible copper cable (ISI MARK) in existing pipe with 6A switch, Ceiling rose and 3mm thick hylam sheet covering to switch control box including all labour charges etc., complete for light, bell, fan and exhaust fan points in Non-Residential Buildings.	03 Points		
	Total Amount			
	CGST @ 9%			
	SGST @ 9%			
	Grand Total			

Terms and Conditions:

1. The bidder shall be authorized dealer / experienced contractor in supply and installation of electrical equipment.
2. The quoted rates shall be inclusive of supply, installation, transportation, testing, commissioning, taxes and all incidental charges.
3. All materials shall be of approved makes and conform to relevant IS standards.
4. The work shall be executed as per instructions of the Engineering Department.
5. The installation shall include complete accessories such as copper piping, wiring, brackets, and fittings.
6. The work shall be completed within the stipulated time after issue of work order.
7. Payment will be made only after satisfactory completion and certification by the Engineering Department.
8. The supplier shall provide warranty for supplied equipment.
9. The University reserves the right to accept or reject any or all quotations without assigning any reason.

Note: “The sealed quotations, superscribed as ‘Quotation for Quotation for Supply & Installation of AC & Cuboid Ceiling Fan – YVU, Kadapa’, shall be sent by post or courier and delivered to the Office of the Registrar, Yogi Vemana University, Kadapa, on or before 23.04.2026 during office hours.”

I/c REGISTRAR

REGISTRAR
YOGI VEMANA UNIVERSITY
KADAPA-516005.

Copy to the Director, IT & Networking Cell, YVU, Kadapa with a request to place the call letter in the University
Web site.
Copy to Notice Board.
Copy to file

