



YOGI VEMANA UNIVERSITY

Vemanapuram, Kadapa – 516 005 (A.P., INDIA)

No. YVU/ED/KDP/PE/JTO/ Admin. Building / Miss. Civil Works / Web Quotation/ 2026-27,
Dt.17.04.2026.

To,

All Reputed Firms / Contractors.

Sub: Yogi Vemana University, Kadapa- Engineering Department – Providing Painting to inside and outside corridors and other miscellaneous Civil allied works at the Administrative Building, Yogi Vemana University, Kadapa– Calling for Quotations – Reg.

--o0o--

Sealed quotations are hereby invited from reputed, experienced civil contractors / agencies for the work of “Providing Painting to inside and outside corridors and other miscellaneous Civil allied works at the Administrative Building, Yogi Vemana University, Kadapa.”

Details of Requirement:

S.No.	Description of Item	Qty	Unit	Rate	Amount
1	Dismantling, clearing away and carefully stacking useful materials for re-use and disposal of unserviceable materials with 100m lead as directed by Executive Engineer duly taking actual premeasurements before dismantling including all labour charges , etc., complete	0.70	Cum		
2	Filling with carted coarse sand in trenches, sides of foundations and basement with initial lead in layers not exceeding 15cm thick, watering and ramming including cost and conveyance of water to work site and all operational, incidental, labour charges, hire charges of T&P etc., and complete for finished item of work (APSS NO.309&310)	0.20	Cum		
3	Labour Charges for removing and re-laying with complete servicing of the upvc plumbing materials including cost and conveyance of all materials to site, incidental, operational and all labour charges etc., complete for finished item of work in all floors.	2.0	Days		
4	Plain Cement concrete Grade M20 - Nominal Mix using 20mm metal hand mixing from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc. to site including all charges laying concrete in foundations and under flooring bed, ramming in 15 cm layers finishing top surface to the required level curing etc., and complete for finished item of work.	0.70	Cum		
5	Plastering 12mm thick single coat in CM(1:5) using screened sand including cost and conveyance of all materials like cement, sand, water etc., to site and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, curing as directed by Engineer-in-charge etc., complete for finished item of work (SS 901,903 & 904)	6.50	Sqm		
6	Plastering 20mm thick single coat in CM(1:5) using screened sand including cost and conveyance of all materials like cement, sand, water etc., to site and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, curing as directed by Engineer-in-charge etc., complete for finished item of work for basement. (SS 901,903 & 904)	3.60	Sqm		
7	Earth work excavation for foundations (Manual Means) of buildings, septic tank, sump, compound wall in ordinary soils and depositing on bank with an initial lead of 10m and depth up to 3m including all operational, incidental, labour charges such as shoring, sheeting, planking, strutting etc., and complete for finished item of work excluding dewatering charges etc., as per SS 20 B (APSS 308)	1.70	Cum		

S.No.	Description of Item	Qty	Unit	Rate	Amount
8	Filling with useful available excavated earth (excluding rock) with a lead of 50 m in trenches, sides of foundations and basement with initial lead in layers not exceeding 15cm thick, watering and ramming including cost and conveyance of water to work site and all operational, incidental, labour charges, hire charges of T&P etc., and complete for finished item of work (APSS NO.309&310)	1.50	Cum		
9	Plain Cement concrete (1:4:8) using 40 mm metal with hand mixing upto Plinth level from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc. to site including all charges laying concrete in foundations and under flooring bed, ramming in 15 cm layers finishing top surface to the required level curing etc.,and complete for finished item of work.	0.10	Cum		
10	Brick masonry for panel walls in superstructure with CM (1:8) prop: (Cement:Sand) using fly ash bricks of size 230mm x100mm x 60mm from approved source having minimum crushing strength of 50 Kg/Sqcm. including cost and conveyance of all materials like cement, screened sand, bricks, water etc., to site, labour charges, like mixing cement mortar, scaffolding charges, constructing masonry, lift charges, curing, etc., and complete for finished item of work.	0.13	Cum		
11	Supply & application of one coat of acrylic emulsion paint having VOC (Volatile Organic Compound) content less than 50 grams/litre as approved by Engineer-In-Charge, to give an even shade after thoroughly brushing the old surface to remove all dirt and remains of loose powdered materials, for internal walls including cost and conveyance of all materials to site, sales & other taxes, incidental, operational and all labour charges etc., and complete for finished item of work in all floors.	580.00	Sqm		
	Total Amount				
	CGST @ 9%				
	SGST @ 9%				
	Grand Total				

Terms and Conditions:

1. The bidder shall have relevant experience in civil maintenance and repair works.
2. The quoted rates shall be inclusive of all materials, labour, transportation, taxes, and incidental charges.
3. The work shall be executed as per standard specifications and instructions of the Engineering Department.
4. The work shall be completed within the stipulated time after issue of work order.
5. Payment will be made only after satisfactory completion and certification by the Engineering Department.
6. The contractor shall ensure quality workmanship and proper finishing.
7. Any additional works shall be carried out only with prior approval.
8. The University reserves the right to accept or reject any or all quotations without assigning any reason.

Note: "The sealed quotations, superscribed as 'Quotation for Miss. Civil Works at Admin., Building – YVU, Kadapa", shall be sent by post or courier and delivered to the Office of the Registrar, Yogi Vemana University, Kadapa, on or before 25.04.2026 during office hours."


I/c REGISTRAR

REGISTRAR
YOGI VEMANA UNIVERSITY
KADAPA-516005.

Copy to the Director, IT & Networking Cell, YVU, Kadapa with a request to place the call letter in the University Web site.
Copy to Notice Board.
Copy to file.